Date: 2019

OK


Sub Project Name:

Tash gozar Check Dam

Tash gozar Village


Saripul Sub River Basin





Site Plane






JOBS	NAME	POSITION	SIGNED		
DRAWING BY			1		All dimention is in Centimeter
SURVEY BY	Sayed Wahid Ahmad	MANAGER OF PLANS & ENGINEERING SERVICES	77	,	SARI PUL SUB RIVER BASIN
DESIGNED BY			1/2/20	PROJECT NAME:	TASHGUZAR CHECKDAM
CHECKED BY	ENG. NAJIBULLAH "HAYAT"	HEAD OF PLANS & ENGINEERING SERVICES	T. J.	TYPE OF PROJECT:	MASS CONCRETE RETAINING WALL
APPROVED BY	ENG. SAYEED ROHULLAH	DIRECTOR OF SARI PUL		LOCATION:	TASHGUZAR VILLAGE CENTER OF SARI PUL PROVINCE
AFFROVEDBI	"SHAHAB"	SUB RIVER BASIN	Lui	NUMBER OF PAGES:	0.1











Cs2






JOBS	NAME	POSITION	SIGNED		
DRAWING BY			1		All dimention is in Centimeter
SURVEY BY	Sayed Wahid Ahmad	MANAGER OF PLANS & ENGINEERING SERVICES	Ita.		SARI PUL SUB RIVER BASIN
DESIGNED BY			THE THE	PROJECT NAME:	TASHUZAR CHECKDAM
CHECKED BY	ENG. NAJIBULLAH "HAYAT"	HEAD OF PLANS & ENGINEERING SERVICES	Lita	TYPE OF PROJECT:	MASS CONCRETE RETAINING WALL
APPROVED BY	ENG. SAYEED ROHULLAH	DIRECTOR OF SARI PUL		LOCATION:	TASHUZAR VILLAGE CENTER OF SARI PUL PROVINCE
NO.ED DI	"SHAHAB"	SUB RIVER BASIN		NUMBER OF PAGES:	0 2







PROJECT NAME:

TYPE OF PROJECT:

NUMBER OF PAGES:

LOCATION:

HEAD OF PLANS & ENGINEERING SERVICES

DIRECTOR OF SARI PUL

SUB RIVER BASIN

TASHUZAR CHECKDAM

MASS CONCRETE RETAINING WALL

TASHUZAR VILLAGE CENTER OF SARI PUL PROVINCE

03

ESIGNED BY

IECKED BY

PROVED BY

ENG. NAJIBULLAH "HAYAT"


ENG. SAYEED ROHULLAH "SHAHAB"

MINISTRY OF ENERGY AND WATER

NORTHERN RIVER BASIN

SARIPUL SUB BASIN


Sec A-A




JOBS	NAME	POSITION	SIGNED		
DRAWING BY			XX	/	All dimention is in Centimeter
SURVEY BY	Sayed Wahid Ahmad	MANAGER OF PLANS & ENGINEERING SERVICES	-12	1	SARI PUL SUB RIVER BASIN
DESIGNED BY			XAD.	PROJECT NAME:	TASHGUZAR CHECKDAM
CHECKED BY	ENG. NAJIBULLAH "HAYAT"	HEAD OF PLANS & ENGINEERING SERVICES	3	TYPE OF PROJECT:	MASS CONCRETE RETAINING WALL
APPROVED BY	ENG. SAYEED ROHULLAH	DIRECTOR OF SARI PUL		LOCATION:	TASHGUZAR VILLAGE CENTER OF SARI PUL PROVINCE
	"SHAHAB"	SUB RIVER BASIN	The state of	NUMBER OF PAGES:	0 4









JOBS	NAME	POSITION	SIGNED		
DRAWING BY					All dimention is in Centimeter
SURVEY BY	Sayed Wahid Ahmad	MANAGER OF PLANS & ENGINEERING SERVICES	1		SARI PUL SUB RIVER BASIN
DESIGNED BY			20	PROJECT NAME:	TASHGUZAR CHECKDAM
CHECKED BY	ENG. NAJIBULLAH "HAYAT"	HEAD OF PLANS & ENGINEERING SERVICES	34	TYPE OF PROJECT:	MASS CONCRETE RETAINING WALL
APPROVED BY	ENG. SAYEED ROHULLAH	DIRECTOR OF SARI PUL		LOCATION:	TASHGUZARVILLAGE CENTER OF SARI PUL PROVINCE
ATTROVEDBI	"SHAHAB"	SUB RIVER BASIN	La Colonia	NUMBER OF PAGES:	0 6





The essential equipment to be made available for the Contract of **Tashguzar Check Dam** by the successful Bidder shall be:

S/N	Type of Equipment's	Required Number
1	GCB (Small Excavator)	1
2	Jack Hummer Excavator For Hard Excavation (Rock)	0
3	Double Drum Vibratory Rollers Compactor	1
4	Water Tanker (about 15,000 liter capacity)	2
5	Tractor with Blade	0
6	Dump Truck (about 10 Cub capacity)	5
7	Reversible Plate Compactors	2
8	Vibrator	2
9	Concrete Mixer	3
10	Generator 10Kw	2
11	Water Pump with 1000 m pipe (Capacity 20 Lps)	2
12	Total station	1
13	Auto Level Machine	1
14	Measuring Tape	3

Bidders are allowed to propose different equipment with sufficient information to establish that their capacity is equivalent or more that the above.

Note: Costly equipment's (e.g. 1, 4 and 5) may be deployed on "As and When required" basis.

Qualifications and experience of key personnel proposed for administration and execution of the Contract. [Attach biographical data. شایستگی و تجارب پر سونل کلیدی پیشنهاد شده قرار دی برای اداره و انجام کارها.

Position موقف	Qty	Years of experience (general)* سال های تجارب(بشکل عموم)	*Years of experience in proposed position سالهای تجربه کاری برای رشته پیشنهاد شده
(a) Project/Contract Manager (One)	1	5	3
(b) Irrigation cum Survey Engineer (One)	1	5	3
(c) Site Engineer cum Safety supervisor (1) - one per site	1	5	3
(d) Safety Engineer	1	4	3
(e) Geo Technical Engineer	1	4	4
(f) Q/C Engineer	1	5	3

Please attach CV and university Certificate of the above persons



SUMMARY BOQ OF Tash Guzar Check Dam (Check Dam Template Structure)

No	Item bill of quantity	Quantity	Unite	Unit Rate (Af)	Total Cost (Af)
1	Site Stripping, Cleaning and Grubbing: 15cm thick site stripping / clearance to layout the work before actual excavation which includes clearing of all herbs and shrubs, boulders as per the dimension of the structure	1	LS		T.
2	Ordinary Soil Excavation: Excavation in ordinary soil (in canal /river bed etc.) and disposal of surplus material up to a maximum distance of 500m or as directed by site engineer.	3850	M ³		
3	Air-Entrained Mass concrete(M200): Supplying, Placing adding boulders, compacting and curing Air- entrained Mass concrete with 4.5 % to 7% of aired Vellums by adding approved admixtures, including formworks as per relevant drawing, specification and to the complete satisfaction of the site engineer.(%age of boulders in the mass concrete should not be more than 40% of total volume, also the size of the boulders should not be neither more than 1/5 th the literal dimension of the structure element, nor 20 cm, whichever is less).	1636	M ³		
4	Plaint Cement concrete(pcc) (M200): Supplying, Placing, compacting and curing Airentrained PCC M-20 with 4.5 % to 7% of aired Vellums by adding approved admixtures, as per relevant drawing, specification and to the complete satisfaction of the site engineer	140	M ³		
5	Joint preparation at each 15m: Construction of expansion joint at every 15 m with 20 cm wide PVC water stop and cork filing including all materials and labors all as per relevant drawing, specification and complete satisfaction of site engineer.	40	M		
6	Air-Entrained Reinforced Cement concrete (M250): Supplying , Placing , compacting and curing Airentrained RCC M-25 with 4.5 % to 7% of aired Vellums by adding approved admixtures including Steel Reinforcement framework , as per relevant drawing, specification and to the complete satisfaction of the site engineer.	51	M ³		
7	Compacted back filing: All backfilling materials shall be will graded granular materials from selected materials of excavation or approved source of borrow pits including compaction to 95% modified proctor in layers of not more than 15 cm thickness in	1600	M ³	A Hancey	

SUMMARY BOO OF Tash Guzar Check Dam (check Dam Template Structure)

	accordance to the relevant drawing and specification and satisfaction of the site engineer.				
8	Gabion basket (1x1x1m): Provide, install and fill the gabion basket (1x1x1) m with stone in place, having mesh size not more than (80x100) mm as per relevant drawing, specification and complete satisfaction of the site engineer. (2.7 to 3) mm galvanized mild steel wire should be used for the mesh with zinc quantity not less than 260 gr/m2 and (3.4 to 4) mm galvanized mild steel wire with zinc quantity of not less than 275 gr /m2 for the frame. The gabion boxes shall be fabricated 'Maccaferri' type or equivalent supplied by an approved manufacturer. The cage shall be constructed with 2.2 mm dia. Galvanized mild steel wire.	15	M ³		
9	Graded Gravel Filter: supplying , placing and compacting granular filter materials under gabion basket as per relevant drawing as specification .	3	M ³		
10	Stone Masonry 1:4 Providing and laying random rubble and coursed stone masonry with cement sand mortar 1:4 as per relevant, Specifications and to the complete satisfaction of the site engineer.	500	M ³	No.	
11	Wipe holes 3": providing and installing pvc wipeholse with per relevant, Specifications and to the complete satisfaction of the site engineer.	60	М		
12	Stone Sign board: Preparing and installation of stone signboard specification and complete satisfaction of the site engineer.	1	LS		

تصدیق کننده : رئیس حوره فار عی دریانی سربل

ترتیب کننده: انجنیر وحید (هاشمی)

تالند : رئیس عمومی حوزه دریایی زون شمل میراند : رئیس عمومی حوزه دریایی زون شمل میراند : رئیس عمومی مورد دریایی زون شمل میراند : رئیس عمومی حوزه دریایی زون شمل

	سوم	0 0
	دوم	اولویت بندی پروژه
	اول	اولويد
350	تعدادمستفيدشونده گان آب	
34560	ت پروژه تحت پلان تخمین به افغانی	قيمد
24	بهبودوضع أبيارى	کتار
104	بعدازپروڑہ	مساحت تحت آبیاری به هکتار
80	قبل ازپروژه	مساحث
0.07	طول کانال به km	
0	جریان اعظمی کانال m³/sec	
200	دار جریان اعظمی دریا m³/sec	مة
10'45"	عرض البلد	
20',42"	طول البلد	
684	ارتفاع از سطح بحر	
آب بار ا	منبع تغذيه	
1	تعدادمير اب باشمي ها	
خوب	امنیت منطقه	
مس کانکر	نوع ساختمان موردضرورت	
اوسون س	7.th. 60.1	
مركز	و لفنو الى	موقعيت
سر با	r Kr	
سرپن چکدم تاش	اسم پروژه	
	104 80 0.07 0 200 10'45" 684 اب بار ا 1 مس كاتكر مس كاتكر مركز	اول اول اول اول اول اول اول اول البلد ارتفاع از سطح بحر ارتفاع از سطح بحر المنيت منطفه المنيت المنيت المنطقة المنطقة المنيت المنطقة المنيت المنطقة المنطق


شماره

4

ملاحظات

فارمت برای خانه پری پروژه چکدم تاشگذر ریاست حوزه فرعی دریایی (سرپل بالایی)

تائید: ریس عمومی حوزه دریایی شمال.



2	1700				وری وتانیدی ادارات زیربط	منظ
امضاع	وظيفه		اسم	A A	مشخصات	شمارت ا
	مدیر برنامه ها انجنیر تاسیسات آمیرتنظیم آب		سیدو حیداحمد امیر حسین محمدیعقوب		سروی کننده	1
	مدير برنامه ها		سيدوحيد احمد		دیز این کننده	2
	رئيس حوره دريايي	(بالو	سيدروح الله (ش	٠	تائیدریاست حوزه فرعی دریای	3
دههوری اسلامی افغانی	Ty ac Energy & Water	apriles.		شمال	تائیدریاست عمومی حوزه دریایی	4
3 guille and a second	2012	•			تاميدمقام ولابت	5
ر المراجع المر	Special River	1		-	منظوری معام وزارد	6
100						
1. 64 2 3. 3						

Title Work plan for Tash Guzar checkdam

	Title Work plan for Tash Guza	r chec	kdam		موضوع: جدول پلان کاری برای اعمار پروڑہ چکدم تاشگذر سال 1398																																							
a H	Item Descriptions	Heit	Quantity																				mo	onth	ıs																			
	item bescriptions	Onit	Qualitity		ماه اول			ماه دوم			ماه سوم				هارم	اه چ	Δ.	ماه پنجم			ماه ششم			ماه هفتم				ه هش	ما	ماه نهم			ماه دهم				ماه ياز هم				ماه اول			
ماره	فعالیت ها	واحد	مقدار	W1	W2	W 4 W	W ₁	W2	W3	W4	N ₁	W2	W3	× ×	W2	W3	W4	W1	W2	W3	W4	T A	W 2	W W	W ₁	W2	W3	W4	M C	7 N/2	W D W	W ₁	W2	W3	W1	W2	W3	W4	W ₂	W3	W4	W	× ×	W4 W
1	آماده سازی ساخه برای کار پروژه	LS	1																																									
2	کندنکاری خاک عادی	МЗ	3850																																									
3	مس کانگریت مارک 200 با40%سنگ	МЗ	1636																																									
4	کانکریت بدون سیخ (PCC)	МЗ	140																																									
5	جاینت هادر هر 15الی 20 متر	М	40																																									
6	اهنکانگریت سیخدار (RCC)	МЗ	51													DU-S																												
7	پرکاری عقب دیوار	МЗ	1600																																									
8	نصب گبيون باكس	M3	15																																									П
9	جغل دانه بندی شده	МЗ	3															2000	100	407-0																								П
10	سنگ کاری فرش بند	МЗ	500						1												T	T	T					T	T	T									I				T	П
11	نصب نل های (PVC)	М	60																										I	I													I	
12	نصب لوحه سنگی	LS	1																			I																						

Prepared by:Sayed Wahid Ahmad