Annex 04:

BoQ of 20 Boreholes/water point in Barmal district of Paktika province.

Nº	Description	Quantity for one water point	Unit	Unit cost	Total cost	Number of Boreholes/water point	Total cost
1	AFRDIF hand pumps kite	1	kit			20	
2	4” PVC pipe	10.5	Pcs			20	
3	4” filter	3	Pcs			20	
4	8mm rad with centralizer	17	Pcs			20	
5	Glue for sedimentation of PVC pipe	1	can			20	
6	63mm PVC pipe with centralizer	17	Pcs			20	
7	Cement	6	Bag			20	
8	Gravel Pack	4	M3			20	
9	Send gravel	2	M3			20	
10	8mm nylon rope	3	Kg			20	
11	Drilling	50	M			20	