

# Bill of Quantity for waiting Area

Province: Nuristan		Waiting Area Bill of Quantities Districts of Wama, Noogram, Mandol and Doaba Noristan province.						
project ID:								
Title	No.	Item	Quantity	Unit	Unit Cost	Total Cost for one waiting area	Number of waiting area	Total Cost for 4 waiting area
A1	1.00	SITE PREPARATION	88	M2			4	
A2	2.00	SEMI HARD EXCAVATION LOADING AND UNLOADING	40	M3			4	
A3	3.00	PCC IN FOOTINGS, FLOOR DPC, PATH WAY AND ROOF: MARK 200 (1:1.5:3)	18	M3			4	
A4	4.00	R.C.C of FOOTINGS, RING, RING BEAM, PILLOR, BEAMS, SLAB AND PROFIT WALL: MARK 250 (1:1:2)	39	M3			4	
A5	5.00	STONE MASONARY, MORTOR MARK: (1:4)	48	M3			4	
A6	6.00	POINTING, MORTOR MARK: (1:3)	102	M3			4	
A7	7.00	PLASTER, MORTOR MARK: (1:5)	175.00	M2			4	
A8	8.00	FILLING, INCLODING FOOTING, FLOOR AND RAMP FROM SOIL AND BOLDER	34.00	M3			4	
A9	9.00	WOODEN WORK, DOORS AND WINDOWS	16.20	M2			4	
A10	10.00	EZOGAM FOR ROOF COMPANY KABUL STAR	110.00	M2			4	
A11	11.00	PANTING						
	11.01	Weather sheet for outside 75%	6.00	Gallon			4	
	11.02	plastic destamber color for inside 75%	7.00	Gallon			4	
	11.03	Oil Paint for stone masonary best quality	10.00	Gallon			4	
	11.04	lining for doors and windows best quality	3.00	Gallon			4	
	11.05	plastic emulsion wash rooms beast quality	2.00	Gallon			4	
A12	12.00	PLUMPING WORK						
	12.01	Gutter full size	2.00	Pcs			4	
	12.02	4" P-Trap	2.00	Pcs			4	

	12.0 3	4" PVC PIPE as per site with all fittings	20.00	M			4	
	12.0 4	Plastic tank 500 liter	2.00	Pcs			4	
	12.0 5	PPRC pipe with related fittings with all fittings	6.00	roles			4	
	12.0 6	Pashm shesha	2.00	roles			4	
	12.0 7	wire for pashm sheha fitting	60.00	M			4	
A13	13.0 0	ELECTRICAL WORK						
	13.0 1	Switch Boards	4.00	Pcs			4	
	13.0 2	Holders	9.00	Pcs			4	
	13.0 3	Fans	3.00	Pcs			4	
	13.0 4	Sockets	6.00	Pcs			4	
	13.0 5	Lights	6.00	Pcs			4	
	13.0 6	Electrical wire and Cable as per site	1.00	M			4	
GRAND TOTAL								